



DAV PUBLIC SCHOOL

CHANDRASEKHARPUR, SAILASHREE VIHAR, BHUBANESWAR

(Affiliated to C.B.S.E., New Delhi, Affiliation No. 1530044, School No.-15329)

QUOTATION CALL NOTICE

No. DAV(CSP)/519 /2024

Date 02.02.2024

Quotations in close envelope are invited by the undersigned from registered Agencies/Contractors/Firms for execution of internal sewerage pipe lines and connection to the manhole/chamber of WATCO (Phase-II) in DAV Public School, Chandrasekharpur, Campus-I as per the following terms & conditions and specifications mentioned in the Quotation Form. Interested Agencies/Contractors/Firms having expertise in the above works are requested to submit their **quotations in the prescribed Quotation Form along with details of works undertaken during the last 5 years on or before 09.02.2024 by 1.00 P.M.** The bidders are also required to enclose a D.D. of Rs.50,000/- drawn in favour of **“Principal, DAV Public School, Chandrasekharpur”** payable Bhubaneswar along with the Quotation Form towards the earnest money. The bidders are also required to submit photocopy of the PAN card along with the quotation. The earnest money of the unsuccessful bidders will be refunded within seven working days without any interest. The successful bidder shall be issued the work order with the terms and conditions as mentioned in instructions for the timely completion of the works which shall be treated as an agreement between the school authority and the contractor.

The envelope containing the quotation must be closed and marked **“execution of internal sewerage pipe lines and connection to the manhole/chamber of WATCO (Phase-II) in D.A.V. Public School, Chandrasekharpur”** on the top of the envelope. The quotations received after the stipulated date and time shall not be considered.

The quotations will be opened on 09.02.2024 at 4.00 P.M. The bidders may remain present physically or by authorized representative during opening of the quotations.

The undersigned reserves the right to cancel either any or all the quotations without assigning any reason there for.

MANAGED BY - DAV COLLEGE MANAGING COMMITTEE, CHITRA GUPTA ROAD, DELHI

At- Chandrasekharpur, Sailashree Vihar, Bhubaneswar- 751021 (Odisha)

Phone No. : 0674-2740651, 2740551, Email: davcspur@gmail.com, Website: www.davcsp.org

Instructions to the Bidders:

1. The Bidders are free to visit the site with permission from the school authority.
2. The details of works to be executed as per the quotation form.
3. The rates shall be inclusive of all materials, excavations, labour charges, transportation charges, civil works, cleaning of debris from the premises, all admissible taxes, etc. complete in all respects.
4. The bidders must have valid PAN, GSTIN, GST numbers.
5. The execution of works should be commenced within 10 days from the date of receipt of the work order.
6. During execution of the works heavy machines should not enter into the playground.
7. Adequate precautionary measures should be taken by the contractor during the school hours for safety and security of the students.
8. The time limit for completion of the work is one month from the date of issue of the work order.
9. Payment will be made after completion of the works subject to the satisfaction of the undersigned as well as the works committee.
10. TDS admissible under rules shall be deducted from the bill.
11. Earnest money of the successful bidder shall be refunded at the time of settlement of the bill on completion of the work on due verification of the works committee.
12. 5% of the bill shall be kept as security money which will be paid without any interest after completion of six months on observation of the quality of the works by the works committee.
13. The lowest quoted price after approval of the competent authority shall be continued till completion of the works. No revision of the rate shall be entertained on the plea of increase of market price or for any reason whatsoever.
14. Problems, if any, during the execution of work must be communicated to the school authority in writing.
15. Safety & security of the workmen during the execution of work in the school premises lies on the selected bidder and the school will not give any compensation for any injury or loss of life caused to any workman during the execution of work.
16. The selected bidder will have to enter into an agreement for execution of the work.


PRINCIPAL

Copy to:

1. Website of DAV Public School, Chandrasekharpur.
2. Notice Board of DAV Public School, Chandrasekharpur for information of all concerned.
3. Principal, DAV Public School, Unit-VIII/Pokhariput/Kalinganagar, Bhubaneswar CDA/Gandarpur/Rajabagicha, Cuttack for information with a request to place the notice on their school notice board for information of all concerned.
4. The file concerned.



D.A.V. PUBLIC SCHOOL, CHANDRASEKHARPUR, BHUBANESWAR-21
QUOTATION FOR EXECUTION OF INTERNAL SEWERAGE PIPE LINES AND
CONNECTION TO THE MANHOLE/CHAMBER OF WATCO (Ph-II).

Name of the Agency/Contractor/Firm:

Complete Address:

E-mail:

Mobile No.

Valid Contractor License No.:

TAN/PAN:

(Please enclose copy of license)

GST No.:

TIN:

Past Experience, if any:

(Please enclose copy of certificate in respect of works completed during last five years)

SI.No.	Name of Organization	Works executed	Total amount of contract/works	Name of the contact person	Mobile number of the contact person

Works to be executed at Campus-I

SI No	Description of items	Qty.	Unit.	Rate	Amount
1	Dismantling of Cement Concrete and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres all complete as per direction of Engineer in Charge.				
		58.83	Cum		

2	Excavation of foundation in literate rock or any hard rock (other than granite or disintegrated rock)removed by chiseling including dressing and leveling the bed not exceeding 1.5mtr depth and depositing the soil within 50mtr initial lead as per specification approved by the Deptt. etc. all complete as per direction of Engineer-in-charge.				
		230.77	cum		
3	Supplying all labour T&P for transportation of surplus materials from the site by etc. all complete as per direction of Engineer-in charge.				
		329.80	cum		
4	Supplying all labour,materials and T&P for filling foundation and plinth with sand watered and rammed as per direction of Engineer-in-charge.				
		214.80	cum		
5	Laying of 200mm dia HDPE-Class-3(PN-6) pipe for sewer line including cost of all labour, T & P etc all complete as per specification and direction of Engineer-in-charge.				
a)	200mm dia HDPE-Class-3(PN-6)	66.00	MTR		
6	Laying of 150mm dia HDPE-Class-3(PN-6) pipe for sewer line including cost of all labour, T & P etc all complete as per specification and direction of Engineer-in-charge.				
	150mm dia HDPE-Class-3(PN-6)	156.00	MTR		
7	Supplying all materials,labour and T&P for new/re constructing Man-hole chamber with R.C.C. top slab in (1:1.5:3) mix with foundation concrete (1:1.5:3) inside plaster 12mm. thick with cement mortar (1:3) finished with neat cement punning, 12mm. thick outside plaster excluding earth work excavation in foundation and refilling the cavity with excavated earth etc all complete as per direction of Engineer in charge.				
a)	New construction of Circular Man-hole size (1.20mtr. dia. O/O x 0.90 mtr i/i)	3.00	Each		
b)	New construction of Circular Man-hole size (1.70mtr. dia. O/O x 1.20 mtr i/i)	4.00	Each		
c)	S.F.R.C.M.H. Cover with frame (heavy duty)	19.00	nos		
d)	New Construction of Inspection Chamber (1.1x1.1x0.9) m	12.00	Each		

8	Providing cement concrete (1:3:6) with 40mm size CBHG metal including cost of all materials, labour T & P etc. all complete as per specification & direction of Engineer-in-charge.				
		23.97	cum		
9	Brick work with Fly Ash bricks 25cm x 12cm x 8cm size having crusing strength not less then 75Kg/cm2 in cement mortar (1:4) in super structure per cum.				
		11.94	cum		
10	12mm thick cement plaster (1:6) on brick work including all cost conveyance royalty & taxes etc. comp. to work site.				
		36.83	sqm		
11	Cement concrete (1:2:4) using 12 mm. size hard granite crusher broken metal including watering and curing including cost, conveyance, royalties and taxes of all materials, labour, T&P etc. complete as directed by Engineer-in charge.				
		23.97	cum		
				Total:-	
				or say :-	

In Words: Rupees.....

Certified that the rates quoted above are inclusive of all materials, all admissible taxes, labour charges, transportation charges, civil works, cleaning of debris from the premises etc. complete and abide by the terms & conditions laid down in the Quotation Call Notice No. DAV(CSP)/ 519 /2024 dated 02/02/2024

Date:

Full signature of the party/contractor